



1-800-345-3036
PROPACUSA.COM



THE POD

RAPID DEPLOYMENT SHELTER



COOLING/HEATING POD • SHOWER/RESTROOM

- 42 Square Feet
- 4 Upper and 4 lower D-rings for teathering
- 6" Double Wall Fabric Construction
- 4 Independent DWF walls and independent roof
- 3 Inflation ports
- Overpressure relief valve
- Pin and anchor joints
- Hook-and-loop seals
- Air Gap Insulation
- Inflatable DWF Door with Zipper Closure
- 2 Insulated inflatable window Plugs
- 2 Roll-down windows (Clear/Closed/Mesh)
- 2 HVAC vents, 10"
- Interior hook-and-loop for lights/accessories
- Removable floor
- Exterior hook-and-loop for custom signage
- Patent Pending

SPECS AT A GLANCE:

Open size: 6.5'W x 6.5'L x 7.5'H

Folded size: 36"W x 36"L x 30"H

Inflates in 2.5 minutes

Weight: 211 lbs

2-Person Setup Required



Storage Box: 4' cube

Item #9108

INCLUDED COMPONENTS

These items come standard with the Pod Kit:

POD – 1	Patch Kit – 1
Tie Downs – 1	HVAC Louver Vent – 1
Stakes – 4	HVAC Air Control Valve – 1
Hammer – 1	HVAC Directional Nozzle – 1
Inflator/Deflator – 1	D-Ring w/Hook – 5
Fire Extinguisher – 1	Hook & Loop Sleeves – 5
Air Quality Meter – 1	Carabiners – 5
Indoor Ext Cord, White – 1	C-Sleeve Storage Box – 1
Light – 1	Tactical Duffle Bag – 1